



The Paged AnnualVolume OneA specimen of the composing engine, its plugins,
and the interchange they serve.

|

|

|

Contents

Front matter	i
Part I divider · Ch.1 Anatomy of This Book	1
Ch.2 The Letter	9
Ch.3 The Paragraph	13
Ch.4 The Style	17
Ch.5 The Story	23
Ch.6 Scripts of the World	31
Ch.7 The Apparatus	35
Ch.8 The Object	37
Ch.9 Ink & Light	43
Ch.10 The Effects	47

Specimen No. 3 · paragraphTabStops · leader: dot

No generate-TOC op exists on the wire; the fixture's TOC style is declared, the entries here are set live from the plan. → Appendix A

How to read this bookEvery demonstration is a numbered Specimen. Its label — set in the outside margin, on the Annotations layer, under the Spec-Notes condition — names the wire op, property path, or registry row it proves. Hide Spec-Notes and the ledger becomes a clean annual; show it and every page cites its own evidence.■ demonstrated in full · demonstrated to a recorded limit, with a margin note pointing at Appendix A · not modelled by declaration, listed only in the appendix. Nothing on any page pretends.

Layers, bottom firstGrid · Background · Content · Annotations · Notes-
Prose sits on Content; plates on Background; every label on Annotations.

 Spec-Notes

 Print-only

 Screen-only

The engine, by op group



Anatomy of This Book

In which the volume opens itself on the table: margins, masters, layers, and the apparatus that decides what prints.

Every chapter after this one demonstrates something the engine does to content. This chapter demonstrates what the engine does to the book itself. The pages that follow are their own exhibit: a spread that draws its own grid, a page whose running head is a recorded act of disobedience, a page that is created, reshaped and destroyed without the book ever changing length, and a page that shows the same sentence three ways depending on who is looking. Nothing here is illustration. The hairlines on the next spread sit at the same coordinates the margin preferences declare; the master tiles on page 16 name the seven masters this file actually carries; the layer bands on page 17 are read from the document, not typed. Where the machinery has a limit, the margin says so and Appendix A holds the ledger.

An override, keptLook at the top of this page. Every other body recto in this book carries the running head the B-Body master stamps; this one reads SPECIMENS RECONSIDERED · AN OVERRIDE instead. That head is not typed on this page by this chapter — it is a page-local override recorded in the fixture, and the machinery under it is the demonstration: a page that overrides a master item suppresses the master's copy without detaching from the master. Everything else the master stamps — the folio below, the verso head opposite — keeps tracking the master. Delete the override and the stamped head would return; re-apply the master and the override would still win. One item disagrees; the rest of the furniture does not even notice.

The layer plan, exercised

A layer is a band of stacking order with three switches: visible, locked, printable. This book keeps five, drawn as bands below, bottom first — the grid under everything, the plates over it, the prose over those, and the apparatus on top. While this page was set, a sixth existed: born as Scratch, renamed to Scratch Bench, handed the blue exhibit below, switched invisible and back (the render changed both ways), moved to the bottom of the stack, and removed. The removal is worth reading twice. The engine does not refuse to remove an occupied layer: the layer record goes, and the item keeps a reference to a layer that no longer exists until someone re-homes it — which this page did, to Content, where the exhibit now lives. The overlapping pair beside it demonstrates the other half of stacking: Arrange, front and back, with no geometry change at all.



Left: the exhibit that survived its layer. Right: the marigold plate was sent to back, then brought to front — `reorderElement`, both directions.

The standing bands, bottom first

	Grid
	Background
	Content
	Annotations
	Notes

The Letter

A type specimen does not prove that a face is beautiful. It proves that the engine can ask the face the right questions.

The faces in this book carry real feature tables: EB Garamond answers for swashes, small capitals, old-style figures and seven stylistic sets; JetBrains Mono for the slashed zero; Space Grotesk for tabular figures. The next spread asks for each feature by its property path and shows both states side by side. The terms are strict. A row whose feature the composer actually drives — ligatures, case, position, and every metric transform on the closing page — shows a genuine difference. A row whose feature the wire can only record is printed anyway, twice and identically, with the margin naming the limit. A specimen that hid its second kind of row would be an advertisement.

The feature specimen, continued

ordn · plain | characterOtfFeatures="ordn" (metadata) | characterPosition="OTSuper-
script" on the suffixes (rendered, metric)1st 2nd 3rd 4th | 1st 2nd 3rd 4th | 1st 2nd 3rd
4th

characterPosition · Superscript and Subscript, position-metric size and shiftE = mc2 |
H₂O | Fe³⁺ | log₂ n

swsh · EB Garamond Italic · characterOtfFeatures="swsh" — authoring metadata*Rare
Kingdoms Answer* | *Rare Kingdoms Answer*

ss01 · characterOtfFeatures="ss01" — authoring metadata*Quirky Regard gently* |
Quirky Regard gently

zero · JetBrains Mono (its zero is slashed by design) · characterOtfFeatures="zero" — au-
thoring metadata0 100 2026 0x0F | 0 100 2026 0x0F

hist · characterOtfFeatures="hist" — metadata; the discrete OTF lane carries no hist flag at
allhis historic listens | his historic listens

3The ParagraphLetters make words; the paragraph is where they start to argue. A composer worth the name does not break lines one at a time - it weighs the whole paragraph at once. This chapter watches it do so: the breaks, the keeps, the caps, and the parameters that steer them.

A paragraph is not broken one line at a time. The composer reads the whole of it first, weighs every place a line could end, and charges each candidate for the space it stretches, the word it divides, and the shape it leaves behind; then it chooses the cheapest complete set of breaks. This is the total-fit method Knuth and Plass described in 1981, and it is why a justified column can hold an even colour from its first line to its last. Forbid the hyphen and refuse the stretch, and the same sentences must end wherever the words happen to stop: the right edge frays, and the ragged column tells you, plainly, what the algorithm had been doing for you all along.

Reading the comparisonCount the hyphens in the justified column, then look for the lines they rescue: without them the composer would be forced to stretch a three-word line across the full measure. The ragged column pays the other way - no line is strained, but the silhouette gives up its even edge. The flex itself is governed by the H&J limits - minimum, desired and maximum word spacing, letter spacing, and glyph scaling. The engine parses and honours all three families when it composes the justified column above; none of them is yet a property path on the wire, so the parameter row beneath uses tracking, the spacing control that is. The fixture's body style also declares a 36 pt hyphenation zone. The zone steers ragged hyphenation only - for justified text the engine zeroes it, deliberately, to mirror InDesign - and it too has no wire path, so the comparison you see is the style's declaration at work, not a live write.

```
paragraphJustification = LeftAlign ·
paragraphHyphenation = false
```


4The StyleNothing in this book is formatted by hand. Every paragraph wears a named style, and every style stands in a chain of inheritance that ends at Annual Body. This chapter turns the system on itself: the cascade, live creation and deletion, nested styles, numbered lists, and the rules and tab stops a paragraph can carry.

Live style surgery

This page performed surgery on its own wardrobe. The style these words wear, Field Note, did not exist when the chapter began: `createParagraphStyle` minted it, based on Annual Body, and eight `setStyleProperty` writes dressed the definition - 8.5 pt type, slate ink, a little tracking, half-rhythm space before and after, no first-line indent, flush left, and a next-style pointing back at Annual Body. It was born under the working name Field Memo and renamed in front of you; `renameParagraphStyle` changes only the display name, so the reference every one of these paragraphs holds survived the change. The letterspaced vermilion openers are Field Note Caps, a character style created the same way and applied as a range on each paragraph. A second pair, Scratch Note and Scratch Caps, went through the whole triple - created, renamed, deleted - in the same breath. The deletions are real wire ops, so those styles are demonstrated, not resident: the checkpoint this chapter saves carries no trace of them. The vermilion rule under each paragraph is a range property, not part of the definition. The style-definition door carries eight paths today; font family, leading and rules are not among them - the first two arrive here through the `basedOn` chain, the rule through the range door.

Field Note, created and dressed on this page · `setStyleProperty`: `characterFontSize`, `characterTracking`, `characterFillColor`, `paragraphSpaceBefore`, `paragraphSpaceAfter`, `paragraphFirstLineIndent`, `paragraphJustification`, `paragraphStyleNextStyle`

Bullets and numbering

A bulleted paragraph is a style choice, not typed glyphs. The marker comes from the definition: the default round bullet. Delete the style and the bullets would vanish with it. These two lines were plain body text until two range writes made them a list. Their dash marker is paragraphBulletCharacter, set live.

Bullet List (style) · paragraphListType = BulletList + paragraphBulletCharacter (live)

Three ops govern the list resources. createNumberingList minted Annual Steps, the list both numbered frames opposite are bound to through paragraphAppliedNumberingList. It was born story-scoped, so the lower frame - a separate story - restarted at one; editNumberingList then set ContinueNumbersAcrossStories and the lower frame carries on from the upper. A third list, Scratch List, was created and deleted again: demonstrated, not resident. The lettered entries restart because they live in their own story. An explicit start-at is not a property path on the wire, so a sub-level restarts by story scope here; the margin note records the boundary.

Mix the ink. Set the line. Pull a proof.

Check the margins. Check the colour.

Numbered 1 + appliedNumberingList = Annual Steps · sub-level Numbered 2, paragraphNumberingFormat = a, b, c

Wash the form. Distribute the type. Note the run.

The same list in a second story: born restarting at 1, it continues at 4 since editNumberingList set ContinueNumbersAcrossStories

The Story

A paragraph belongs to a story, and a story is not a frame: it is the text itself, which merely stands in frames for as long as they hold it. This chapter threads one story through four frames, lets another overflow and says so, and teaches frames to balance their columns, grow to fit, wrap around an island, and carry anchored cargo through every edit.

b

Above: the fixture's footnote exhibit — a body frame whose story anchors two live footnotes. The engine reserves their space through a compose, measure, re-compose fixpoint; no mutation on the wire set narrow at will. The story neither grows nor loses. Not a letter appears twice. What you read is the engine. It is reading itself back. In order, frame after frame. It ends low on the recto. With room to spare, as promised. One story, many stands.

A footnote is the page apologising for an interruption it refuses to omit. The engine reserves its space through a compose, measure, and re-compose fixpoint that vertical justification then respects; the rule above the pool comes from the document footnote options, authored in the base fixture because no mutation writes them.¹²

The reservation fixpoint: compose, measure the pool, compose again. An oversized footnote does not yet split across frames — a recorded limit.

Columns, balance, depth, and the first baseline

Three frames, three text-frame preferences: a two-column split with a ten-point gutter, the same split balanced so the columns end even, and a vertically justified box whose inset holds the text off its own stroke. Below them, the six first-baseline policies in identical boxes.

A column is a promise about line length: split the box in two and every line stays short enough to read without effort. The gutter is the fence between them — ten points of it here.

Balancing splits the text so both columns of this box end within a line of each other.

The top of the box. The middle holds its ground. The bottom of the box.

Two columns, 10 pt gutter.

Balanced — both columns end even.

Vertical justify, 10 pt inset off the stroke.

FirstBaselineOffset — the same two words in the same 44 pt box, six ways:

First line	First line	First line	First line	First line	First line
AscentOffset	CapHeight	XHeight	EmBoxHeight	LeadingOffset	FixedHeight

The wrap catalog

Text wrap is the page's negotiation between type and object: the object declares an exclusion, and every line that would have crossed it is measured again against what remains. The mode of the declaration. A bounding-box wraps the object's rectangle; a contour wrap traces the object's edge so the text follows every bay and cove of the island sitting in the middle of the measure — and because its inside edges are open, a hole through the island is open water too. A jump-object wrap concedes the whole band: no line shares a baseline with the object, however narrow it is. A next-column wrap concedes the rest of the column, sending the interrupted line to the top of the following one. And a wrap of none concedes nothing — the text runs beneath the tint as if it were not there, which is to say the text reads through its own veil. Each declaration here was applied to the tint, after this prose was already set: the reflow you are reading is the result of the island's wrap on this page is symmetrical about one fact: the pushed text and the island push each other out of the way, knowing nothing of each other's content. The columns re-measure, the island's measure closes over the water without a case at the foot of the page proves the rule by turning it around — the island's baseline is not an exclusion but the only territory the text is allowed to hold, and everything outside it is given up instead. Between those two poles sit the four tiles above: each one a small weather system in the flow, each declared its own property on a single object, each unyielding to the other.

Clockwise from top left: BoundingBox pushes the measure off the tint's rectangle; JumpObject clears the full band; the marigold island wraps to its own contour, hole open; None lets the text run beneath the veil; NextColumn sends the interrupted line onward.

The island's measure turns the exclusion inside out: instead of excluding the text, it keeps the text only where it can't go — everything outside the island's outline is given up.

Scripts of the World

Latin is one script among many, and a composing engine that stops at it has stopped early. In this chapter the text runs the other way — Arabic and Hebrew from right to left, with digits and Latin nested inside — and then turns on its side, in the vertical Japanese the fixture carries. Where a lane is partial, the margin says exactly how.

Right: the fixture's
vertical exhibit.
Columns run top
to bottom, lines
advance right to
left; the face is
Noto Sans JP at
thirteen points.

No wire op writes
StoryDirection —
the two vertical
stories ship in
the base docu-
ment; everything
around them is
set live.

Inside the col-
umn: the second
run carries a
GroupRuby read-
ing over its base
characters; the
final run carries
kenten emphasis
marks beside each
glyph.

Vertical composition turns the writing frame on its side: glyphs stack down the column and columns advance toward the spine. Kinsoku keeps forbidden characters off line starts and ends; mojikumi tightens the full-width punctuation between them.

Exhibit, fixture-authored: this story was born navigable - a hyperlink text source on paged. media, the cross-reference source that resolves overleaf, and two index markers filed un-

7

The Apparatus

A book is not only its pages; it is the machinery a reader moves by. Links, bookmarks, references and index marks - shown live where a door exists, named honestly where none does.

The exhibit above was born linked; the two spans below were not. Each became a link while this page was set, one `insertHyperlink` call apiece. Consult the living registry for the current capability record. Or turn to the first chapter opener and compare this furniture with its plainer ancestors.

Hyperlinks, read live: 5 — `registry-url`, `back-to-ch01`, `xref-overleaf`, plus 2 authored on this page moments ago (which the wire, honestly recorded, minted under a single shared id). Bookmarks, read live: 3 — Apparatus, Chapter One, Data Tables. No wire op minted these; the fixture did.

44

Specimen No. 63 · `insertHyperlink x2 (v53)` · hyperlinks / bookmarks read live ·

`insertHyperlink` is the apparatus's one live door and it mints URL destinations only — the page-flavoured link above is a `page://` URL by convention, not a `DestinationPage`; true

The apparatus of the annual begins here. See the reconsidered specimens overleaf, or visit paged.media for the living registry.

⁸Specimen notes, reconfirm the object. Jump back to the first chapter to compare settings.

Everything on a page is an object with a stacking order, a transform, corners, a stroke and, sometimes, other objects inside it. This chapter takes one plain rectangle and asks it every question the wire knows how to ask.


Below, five plates were inserted back to front, A first and E last, then rearranged live: A to the front, B to the front over it, A one step forward and one step backward, E to the back, and finally D to absolute index zero. Every overlap you can read is the paint order saying so.





A vermilion, B marigold, C screen blue, D slate, E vermilion 20%. `reorderElement` walked all five targets - front, back, forward, backward, absolute index - six steps, six gated re-

The corner sampler

A frame's four corners are addressed by name - option and radius each, eight property paths. Five kinds, one mixed outline, and one polygon that shows where the addressing ends.




c




The same vocabulary on a polygon: the TopLeft slot rounds every corner uniformly - the four names are rectangle-shaped addressing, and IDML has no per-name mapping for a shape whose corners are not four. The BevelCorner written to TopRight is stored and round-trips; it steers nothing.

Topology and the pathfinder

Each tile in the upper band holds the same shape twice – untouched at left, operated on at right. The lower band feeds overlapping pairs to every planar verb the wire declares.



~~insertPath (closed Bezier blob + open polyline) · pathPointInsert · pathPointSet · path~~



pathPointRemove · pathOpenAt · closePath · joinPaths (two open strokes welded into one)




simplifyPath tol 6 · outlineStroke w6 (the stroke becomes a region) · offsetPath +8. Edit




pathfinderBoolean on fresh overlapping pairs: union · intersect · subtract · exclude (the



The region verbs, one fresh pair each: divide · trim · merge · crop (the top shape is the



outline (edges become open lines) · minus back · faces, keeping only the engine-minted



Ink & Light



Ink is subtractive and patient; light is additive and quick. Where the two share a page, the page needs arithmetic — sixteen kinds of it.

The plate overleaf is one motif set sixteen times: two soft shapes and a marigold square, identical to the last point, except for the compositing arithmetic the square carries. The engine speaks the full InDesign blend vocabulary — Normal through Luminosity — and the plate names every member rather than sampling the flattering ones. The closing page turns to light's other instruments. Two gradients are minted live on the wire and one is edited in place, to prove the ramp is data rather than ink. An opacity ramp steps a vermillion chip down into the paper. And two opacity masks — one reading luminance, one reading alpha — do what no IDML element can. The margin says so plainly, and the export ledger counts the loss out loud.

Hard Light to Luminosity

The second eight trade tone for colour: the last four blend hue, saturation, colour and luminosity rather than darkness.




9 · HardLight



10 · SoftLight



11 · Difference



12 · Exclusion




13 · Hue



14 · Saturation



15 · Color



16 · Luminosity

The Effects

Eight families of borrowed light and manufactured shadow, some sixty property paths between them — and one honest contact sheet.

The verso overleaf is the contact sheet: the same vermilion square eight times, each carrying one family at full expressive settings — drop shadow, inner shadow, outer glow, inner glow, bevel and emboss, satin, feather, directional feather. The recto answers with two compositions that use them in anger, and gives the gradient feather, the ninth instrument, an exhibit of its own. The closing page is the parameter table: for every family, a row of small squares that turn one knob at a time, so the reader can see what each path buys rather than take the panel's word for it. Two limits are recorded where they occur — satin stores an invert flag the rasterizer ignores, and a transparency group's raster bounds can clip a wide overhang that the PDF path keeps. Both stand in the margin and again in Appendix A.

Effects in anger



Display type carrying drop shadow and a screened glow; the moon layers bevel and satin



A feathered slate cloud and a vermillion veil losing its top and bottom edges to the direc-



frameGradientFeather — the fade is alpha, not ink: one bar, opaque to absent.

The Colour

A document's palette is a contract with a press. This chapter reads the annual's seven inks off the live collection, mints and edits new ones in front of you, walks the whole library out of the file as Adobe Swatch Exchange bytes and back in, and finishes at the prepress bench: profiles, proofs, ink aliases, and the defaults a fresh frame is born wearing.

	Annual Ink · process · CMYK 72/62/58/90 — the editorial black, built rich rather than flat K.
	Paper Warm · process · CMYK 2/3/6/0 — the paper simulation every plate sits on.
	Vermilion · spot · a real spot ink, CMYK build 0/85/90/5 — a named separation all the way to the plate; this composite previews its CMYK alternate.
	Vermilion 20% · process · a real CMYK-built tint, TintValue 20 on the vermilion build. Deliberately not an RGB tint: TintValue scales only through
	Slate · process · CMYK 65/45/30/10 — the annotation ink the spec labels wear.
	Lab Marigold · process · Lab 78/15/82 — a true Lab primary, resolved analytically (D50 to D65 Bradford, then sRGB), no profile required.
	Screen Blue · process · RGB 47/111/235 — the deliberate warning specimen: an RGB build in a print document, kept out of the brand group on

There and back — the .ase loop

Three inks were minted for this page and gathered into a group called Annual Loop. The group then left the document: the export door serialised it to 204 bytes of Adobe Swatch Exchange, magic ASEF, version 1.0 — the same file a designer would hand to a colleague on another tool. Then all three swatches and the group were deleted; for a moment the palette genuinely did not hold them. `importSwatchLibrary` read those bytes back. The chips below are painted from the REIMPORTED swatches, resolved by name — which is only possible because the originals are gone. Identity does not ride in an .ase: each ink returned under a fresh Color/u id. The names, the colour spaces, the channel values and the group all did, and Ledger Sea came back still a spot.



Ledger Red · process CMYK 10/95/90/2 · returned as Color/u11 (process)



Ledger Buff · process CMYK 6/12/35/0 · returned as Color/u12 (process)



Ledger Sea · born a SPOT, Lab 42/−18/−28 · returned as Color/u13 (spot)

The loop is the point: a palette is not locked in this file format. What leaves as an interchange library comes back as first-class document swatches, grouped as they left.

The Table

A table is not a grid of rectangles that happen to align; it is a structure the text owns — rows and columns inside a story, with a header that knows to say itself again. This chapter builds one taller than its frame and lets it walk across the gutter, its header and footer repeating at the break; then it takes a cell apart property by property, rebuilds the grid live, and dresses the whole thing in styles.

d

Rebuilding the grid, live

The operations log below is itself the table the operations ran on. It was minted four rows by three columns; a row and a fourth column arrived afterwards, live; a scratch row and a scratch column each existed for exactly two operations — created, then deleted — so the record shows them without the grid keeping them.


The band bench: a header and a footer were inserted and removed again on this small table. Four real ops, net zero — the long table on the previous spread is where the bands stayed to repeat.

One structural door does not exist: a table inside a cell. The wire's insertTable takes a story address and carries no cell qualifier — checked against the generated wire types, not guessed — so a nested table cannot be authored live. Documents that arrive with one render it faithfully; this page simply cannot make one.

The Picture


A photograph enters a document twice: once as pixels the engine must decode, and once as a claim about where those pixels came from. This chapter places the same image through six codecs, keeps an EPS honestly undecoded, and works the fitting model — then shows the inline lane that carries every one of these pictures through the container round trip.

Alpine sunburst at sunrise · Sagui Andrea, Pexels · 2200×1469 px, 801,589 bytes of base-



GIF · 305,084 bytes · 87a, one adaptive 256-colour palette. Look at the apples' shoulders: continuous tone posterises where PNG keeps it smooth.

BMP · 1,281,654 bytes · Windows 3.x, 24-bit, uncompressed — every pixel spelled out; the largest file for the same picture.



CMYK JPEG · 520,203 bytes · baseline DCT, FOUR components, core's default CMYK profile embedded — decoded through the ICC lane, not assumed

EPS · 987 bytes of EPSF-3.0 · recognised, NOT decoded — there is no PostScript interpreter, by declaration. What you see is the frame's own fill standing in: the honest render of content




The crest above arrived as a file of curves — `annual-crest.svg`, fed to the host importer registry and claimed by `paged.draw`. The importer lowered every contour through the same `insertPath` the pen tool commits, so what stands on this page is six native polygons wearing real swatches, not an embedded picture of a drawing. Two of those shapes are compound. The engine fills non-zero, and the importer delivers a compound path as sibling contours, so the annulus first painted as a solid coin; `Compound Path > Make merged` each pair into one polygon and re-wound the inner contour by nesting depth. The paper you can read through the ring is the whole argument of this chapter: a drawing tool that writes the document's own geometry, not a layer above it.


Specimen No. 115 · `media.paged.draw.importer.svg` · `insertPath` ×6 · `makeCompound`—
 the importer's documented envelope is solid colours and geometry - gradients, `<text>`
 and `<image>` in an SVG do not lower; the crest was authored inside that envelope → Ap-

The pathfinder wall

Ten planar verbs as `paged.draw` commands over a live selection. Each column holds the untouched scratch pair above and the same pair after its verb below - the operand order is the selection's, exactly as a menu invocation would read it.




Unite, Subtract, Intersect, Exclude - the shape modes; the first-selected quad keeps its identity and receives the result. Fifth column: Divide splits the pair into every planar




Trim, Merge, Crop, Outline, Minus back - the region verbs, resolved over one planar arrangement with ownership following the z-order you see: the blue diamond sits in front,

The engine's planar ops were shown raw in Chapter 8. This wall is the COMMAND lane over them: the same arrangement kernel, reached through the registry a menu bar, a palette and a shortcut all share - which is why every result here also answers undo as a single step.



The appearance stack


An IDML frame owns one fill and one stroke. The stack below is plugin metadata plus a bake: the left blob is LIVE (stack on the envelope, front-most layer on the frame), the right one is the same stack lowered to a carrier group of single-paint items.



Two identical blobs, each carrying +1 fill and +2 strokes over their own paint, one stroke reordered by Appearance: Reorder layer. The left is live metadata; the right was group-baked into a carrier plus 3 derived single-paint layers. They render alike - that is the bake's




Three tiles, one saved style. Apply linked all three; a direct recolour of the first marked it overridden without breaking its link; Redefine pushed first blue, then slate, through every link it found. The third tile broke its link after the blue pass - it keeps that appearance while its neighbours moved on. A style that only copied values would be a clipboard; the






Repeats and symbols

Two ways to say 'again'. A repeat transforms copies of a source and stays re-plannable; a symbol is a named definition whose placed instances follow a redefine - until one breaks its link on purpose.

Left: one petal, radially repeated 8 times on a 40 pt ring, every instance rotated to follow - then EXPANDED, so the rosette is now plain artwork with no recipe. Middle: a chip gridded 3x3; its re-plan by Update was REFUSED by this engine at the group re-create, and the margin note carries the sentence - the 3x3 field stands as made. Right: a pennant




One badge defined from the two source shapes at far left and placed three times - each instance re-emitted native geometry with a per-leaf link. The source then turned blue, and no badge followed: an instance is STATIC (core has no symbol node and no duplicate op), so a new look travels only through Redefine's rebuild - which this engine refuses at the instance-group re-create, the same one-batch dissolve-and-regroup seam the margin note




Type on a path, corners and kin

A story freed of its frame and flowed along a curve; rectangle corners restyled live; and a selection that finds its own family by fill.



The sentence above flows an ordinary story along an ordinary path - `attachTextToPath` took the story this page typed, styled and then freed by deleting its frame (no on mints a bare story that works like in the movie). A search bar also attached and detached, detach



Rounded, Bevel, Fancy - three of the five live-corner presets, each an eight-write batch onto the rectangle's real `frameCornerOption` and `frameCornerRadius` properties, 12 pt




Eight tiles, three of them vermillion. One vermillion tile was selected by hand; `Edit > Select same > Fill` grew the selection to 97 elements - not just the three tiles but every carrier of that swatch reference in the DOCUMENT, because `select-same` reads the fill reference,

The Darkroom

Every correction in this chapter is honest about where it lives. An adjustment in `paged.image` is session state — a scene layer composited over the frame, gone the moment the document reloads. What persists is the loop: adjust the pixels, export them through the bundle's own encoder, and commit the exported bytes back into the frame as inline image data. Every photograph on the pages that follow went through that loop before it was allowed to stay.



Place writes a link and a fitting; ingest decodes the placed bytes into the plugin's session; adjust runs the registered kernel chain on the GPU; composite paints the result over the frame as a Stage-A scene layer. Four of the five stations touch only the session. Commit is the exception and the point: the exported pixels re-enter the document through `replaceImageBytes`, the inline lane the container round trip preserves.



Each caption names the family, the dispatch id from the kernel registry, the panel setting, and the byte count of the committed export — the number that proves the tile you are looking at is document data, not a live preview. Kernels run once, in the session; what persists is what came back through the loop.

gaussian blur · conv.gaussian_h + conv.gaussian_v
4 px20,965 B committed

unsharp mask · conv.unsharpamount 2.592,909 B committed

edge detection · conv.find_edgesstrength 1615,733 B committed

Eight tiles are parameter kernels — the slider writes a value, the export runs the chain, nothing touches the session source until the loop commits. The edge-detection and halftone tiles are effect kernels: their buttons apply destructively into the engine-held source, journaled in the plugin's own undo. Both kinds leave the document untouched until replaceImageBytes — which is why the loop, not the kernel, is this chapter's law.

filter gallery · gallery.
halftone6 px dots at 45
deg615,733 B committed

bool (4) and or xor notcast (2) premultiply unpremultiplyrel (6) eq ne lt le gt ge-geom (10) flip_h flip_v rotate90_cw rotate90_ccw crop warp_backward rotate_bilinear move_selection offset mosaicgen (9) solid checker linear_gradient radial_gradient pattern angular_gradient reflected_gradient diamond_gradient noisegallery (12) kuwahara posterize_edges glowing_edges halftone grain diffuse crosshatch bas_relief threshold_ink stained_glass glass texturizermorph (2) dilate eroderank (3) median3 despeckle dust_scratchesresample (3) nearest mitchell lanczos3

Retouch — painting from the image

The clone stamp and the healing brush are the brush with a different paint layer: the clone copies a window of the image from an alt-clicked anchor; the heal runs the same stroke and then tone-matches it in the gradient domain, so the patch takes on the destination's light. Content-aware fill synthesises a marquee'd region from the rest of the picture, coarse

BEFORE · as shot · 168,209 B inline · two retriever puppies, Chevanon Photography, Pexels

AFTER · clone + heal transplant flowered turf into the upper meadow; content-aware fill lifts a flower cluster from

The anchor click is a separate interaction from the stroke — alt-click sets the source and deposits nothing, because painting the anchor is the one thing a retoucher never wants. The heal's correction is the membrane field matching the source–destination mismatch on the dab's boundary; where the window runs off the image it falls back to a plain clone and says so in the panel. Attribution on this page is measured twice: each landing is read from the panel's status line, and the committed export is byte-compared against an identity baseline taken before the first stroke.

PSD — the file that must survive

A PSD is somebody's working file, so the rule is preservation first: the reader retains every block it parses, unknown blocks opaquely, and a zero-edit save is byte-identical — an invariant proven in the plugin's own gates over a synthesized corpus and a 64-case property test, PSB included. What follows is the annual's own three-layer fixture through that


THE PARSED RECORDS
Backdrop — opacity 100%
Plate — opacity 78%
Signal — opacity 63%
Edited through the panel: Signal: 63% → 30%. The edited PSD exported as annual-layers.psd, 27,654 bytes — a record edit carried on the retained parse. The canvas shows the import-time flatten; a layer edit lands in the EXPORTED file, not in a live re-composite — the panel states this limit where the edit is made.

annual-layers.psd · 27,654 B on disk · composite
committed as 481,099 B of inline PNG


Three layers — Backdrop (normal), Plate (multiply), Signal (screen) — assembled by the crate's own spec builders, mask-free by the layer-import tier's documented envelope. The preservation claim on this page is a citation, not a re-run: byte-identity at zero edits is the gate image-psd holds in its own test suite, and what this page adds is the editor reach — list, edit, export, through the panel a designer actually touches.

The Ledger


A spreadsheet in a page document leads two lives, and this chapter refuses to blur them. The live grid you can type into — the one that recalculates under your fingers — is a scene-layer session: it dies the moment the file is saved and reopened. What persists is the workbook itself, travelling in the container as a part, and everything the plugin LOWERS to native content: tables that are real tables, charts that are real paths and label frames. The pages that follow lower ten charts, pour a range, spill a formula, walk a day-book across a gutter, and end by asking the container what it actually carries.




area — 8 native paths, 12 label frames




pie — 8 native paths, 5 label frames



donut — 9 native paths, 5 label frames








scatter — 8 native paths, 8 label frames



radar — 12 native paths, 12 label frames

How to read the wall: each specimen is the plugin's own lowering, scaled uniformly by one transform per chart — the geometry is the engine's, the slot is the page's. The colours are document swatches the lowering minted at content-addressed ids, so two charts sharing an axis grey share one swatch.



Formulas, spill, and the roster

The lowered range prints RESULTS: the SUM as 5 and 10, the concatenation as SumProduct, the uppercase call, and the spill range 10–40 that four cells inherited from one anchor. The formatted value is the value — the grid and the page share one format engine, so what you audited live is what went to press.

Table — the function library, by family, counted from the registry at build time.

The continuation — the same story, walking on across the gutter. (No header band could be added on this run; see the chapter notes.) The chain holds the whole day-book — nothing is oversight past the last frame.

The Long Read

HTML and CSS are a writing system for documents, and this chapter treats them as content: an article authored as markup, placed in a frame, laid out by a real browser engine, and printed here beside its own source. The pages that follow thread one source across many frames — including a named sidebar flow — break a forty-row table across three frames with its two-row header repeating, and close on the honest asymmetry of the whole affair: a live render is session state, and only what is baked to native content survives the file being closed.

One source, two flows, four frames

The article declares flow-into: article-flow; its route notes declare flow-into: sidebar-flow. Frames are the real Regions consumers here — the chain below is persisted in the source's envelope and container part, and this page reads the part back as its proof.



The baked lane

The Year the Presses Ran Long

Twelve months, one flood, three second printings, and the first year since the rebuild in which spoilage held under four percent . The long account of how the counts were made.

January to March

The year opened the way press years usually do: cold plates, a cautious first run, and a circulation ledger that had been ruled but not yet written in. By the end of March the house had set 1,840 print copies and logged 620 first opens of the digital edition — a ratio the board called healthy and the pressroom called a ~~warning shot, and called a warning shot~~ and both were right.

What changed in the first quarter was not the volume but the discipline. The dock tally and the run counter were reconciled every week instead of every month, and the difference between them — the honest name for spoilage — stopped being a quarterly surprise and became a Tuesday routine.



bakeWebFrame — this run's receipt: native rectangles 1 native text frames 28 native paths 1 minted swatches 6 (Color/wb-...) readout: Bake to document #1 — 30 n fillPathGradient ×9 dropShadow ×1 baked 30 nat

Everything the bake could not lower honestly it counted and reported instead — the deferred kinds above are the plugin keeping its books straight. What it did lower is ordinary page content now: these rectangles and text frames export to IDML and PDF like anything else in this annual, engine or no engine.

listPagedParts paged/media.paged.web/ → 1 part(s): ueef010/source.json

The Catalog

A catalog is not a page decorated with numbers; it is a database wearing typography. This chapter publishes FROM data rather than decorating WITH it: a forty-eight-row order book registers with a real query engine, its columns become bindings whose expressions the engine writes, and what lands on these pages — live fields, a native table, four barcode symbologies drawn as page geometry — is resolved content, not pasted text. Where the shipped surfaces stop short of the engine underneath, the margin says so.

The source, before any engine touches it — `annual-orders.csv`:

```
id,customer,region,product,qty,unit_price,order_date,sku,ean,upc,url,notes1001,Berg-
feld Booksellers,Alpine,Letterpress poster,120,4.80,2025-01-03,PA-...1002,The Pass
Hotel,Alpine,Seed catalogue,1000,5.60,2025-01-10,PA-2025-1002...1003,Kettner Choc-
olatier,Alpine,Menu card,80,2.10,2025-01-17,PA-2025-1003-A...1004,Quayside Fish
Market,Harbour,Label sheet,220,0.85,2025-01-24,PA-2025-1...1005,Harbour Light The-
atre,Harbour,Shop ledger,60,12.50,2025-02-03,PA-2025-...1006,Mole & Anchor Tav-
ern,Harbour,Concert programme,90,1.35,2025-02-10,PA-2..... 42 more rows
```


A native table, governed

The bound table is not a picture of a grid: the plugin inserts a frame, mints a real Paged table in its story, and pours every cell by table, row and column — one row per record of the order book. It reflows, it styles, and it exports to IDML as a table because it is one. What the shipped panel can WIRE into it is the demo's single unnamed column, and this page prints that honestly rather than dressing it up.

The lowered table — minted with 49 native rows (one header, 48 records) in the demo wiring's one column, trimmed here to eight records because a native table paints past its frame. Every body cell reads #PARSE because the demo wiring binds an EMPTY expression and the engine prints its error token rather than inventing a value. A table binding's column spec has no authoring surface yet — the authoring row offers variable, image and barcode kinds only — so this demo shape is the only table a designer can define today, and the page prints it as it resolves.

The governance ledger — the dataset panel's own answers: the query engine never reached ready on this lane — no table lowered and no governance readout ran; the frames above say so.

Data sets and the refresh

A binding is live in both directions: the record card three pages back can be re-resolved against any record, and the values it shows at a moment can be captured as a named data set and applied back later — many fields, one undo step. The ledger below is this page's lab notebook: each line was read from the document's own placeholder door at that step of the drive, and the card was left as the chapter found it.

Stepped to record 3 of 48 — the engine re-resolved every binding against that record and the card read `customer = Kettner Chocolatier · unit_price = 2.1`.

captured “Order 1001 — as imported” (record 1) — 1 variable(s)
 captured “Order 1003 — Kettner” (record 3) — 2 variable(s)
 before apply · `customer = Bergfeld Booksellers · unit_price = 4.8`
 apply “Order 1003 — Kettner” → 3 written in ONE undo step · skips:
 none after apply · `customer = Kettner Chocolatier · unit_price = 2.1`
 refresh from sources → the fields moved to `customer = Bergfeld Booksellers · unit_price = 2.1` — the refresh loop re-resolved Overridden fields back to the live record; recorded as measured
 apply “Order 1001 — as imported” → 3 written · `customer = Bergfeld Booksellers · unit_price = 4.8`

Asked “what changed since last sync?” — the panel answered “changed since last sync: 0 changed · 0 unchanged · 3 added”: a first report is the baseline, so every binding arrives as added; the data itself has not moved.

Locale en → de left the bare-column price display unchanged (4.8) — a bare field reference renders the raw value; only the NUMBER/CURRENCY/PERCENT/DATEFMT format family consults the locale, and the expression page ahead drives that family. Measured, so said.

Specimen No. 180 · preview stepper (resolve_at, of-N bound) · captureDataSet / apply-

The price-band RULE this page planned (D-13: a data condition applying a named cell style through the engine's evaluate_rule and the minted rule cell style) is engine-shipped

The Manuscript

A manuscript arrives as a .docx, and this chapter treats that arrival as a PLACE, not an open: the Word file is poured into the open layout as native Paged content — real paragraphs, real character runs, styles synthesized from the document's own word/styles.xml — while the source bytes travel beside it as a container part. Nothing about the result needs the plugin to render, and nothing about the source is thrown away. The spread that follows pours a full circulation report and reads it here, tier by tier; the closing page tells the save-back story straight — what patches, what carries verbatim, and how to tell which happened.

annual, and the counting rules themselves are documented, in more words than they deserve, at docs.paged.media. Subscribers moved between the two channels all year without ceremony and the report treats them as one readership with two doors. Largest single run (Q4) 2,390 copies Spoilage, full year 3.7 percent Editions gone to a second printing 3 Next year's targets are set the way this house has always set them: one more route, one fewer excuse, and a spoilage figure that keeps its head below four. The presses are ready. So is the dock.

Tiers continuing here: the circulation table keeps its gridSpan title row and vMerge'd Alpine cell; the plate mark arrives as an anchored image frame that paints the missing-image marker — the embedded PNG's bytes have no URI the anchored-frame door can fetch — and it overlaps the rows beneath it; “paged.media/annual” and “docs.paged.media” are the

Specimen No. 184 · linkFrames → one story across the spread (asked, not assumed) ·

The pour arrives in one frame sized to the .docx's own section margins; this spread re-framed and threaded it — ordinary layout, and the only kind of move there is. → Appen-

The last chapter of the body is about leaving well: what the press needs, what the container carries, and what every exit admits it cannot take.

Six pages follow. A plate draws the sheet's anatomy — trim, bleed, marks — in the page's own native geometry. A preflight runs the real PDF export door against this very document and prints what it reported. The container is opened and its parts are listed, written and read back through the same doors a plugin uses. The loss ledger prints, verbatim, what the IDML interchange twin must leave behind. And the exit inventory names every artifact this book has already sent into other applications' hands. Two doors are deliberately absent from those pages. `paged.pdf`'s import opens a PDF as a new native document, and `paged.publish`'s IDML open does the same for an interchange package — and both REPLACE the document they are invoked over. That is the correct shape for an import (a PDF becomes the document), and it is exactly why neither runs inline here: invoking either would end this book at this sentence. They are doors out of this build, exercised as exit paths at assembly — export, reopen, compare — and their import lanes are proven where imports are proven, by their own journeys. A demonstration that pretended otherwise would be a screenshot, not a specimen.

The preflight

A preflight is the press asking its questions early. While this page was built, the document you are holding went through the real export door — `client.exportPdf`, standard PDF 1.7, the same begin-page-finish session the File menu drives — and answered for every page it had. The serialized proof came back 28.1 MB long and was discarded on the spot; what this page keeps is the export's judgment: 27 diagnostic line(s) and 27 structured finding(s), printed verbatim below.

Two codes carry most preflights. `font_not_embeddable` names a face whose `fsType` licence forbids embedding: the exporter follows its policy — outline the glyphs, or fail the export — rather than ship a file the licence disallows. `image_missing_bytes` names a placed link whose pixels never arrived; the page paints its proxy, and a proof would too, so the finding says it before the press does. Each finding arrives with a severity and the page it was raised on, which is what turns a warning list into a work list. Beneath the findings runs the flat diagnostics channel — 27 line(s) on this run, the first of them: “font “Noto Sans Hebrew” is not available; a substitute face was used”. The findings are the structured half of the same story (protocol 62 carries both), and this document elects to print the structured one.

Table 20.1 — preflight findings, exactly as the `pdfExported` reply carried them.

The loss ledger

Two exports leave this document. The .paged container keeps everything — the native model part carries the whole scene, masks and all. The .idml interchange twin is for other hands, and its writer holds a harder line: an unmutated document round-trips byte-identically (measured on the real corpus: 99 of 99 packages, 11,876 entries, zero gaps), a mutated one differs only where the edit touched — and whatever IDML cannot express is not smuggled or silently dropped, it is NAMED, in the export reply itself.



The specimen: a vermillion plate fading through an opacity mask whose artwork is the Annual Ramp. It stays on this page — paged-native, resident, and named by the export below as exactly what the interchange twin cannot carry.

Table 20·3 — `idmlExported.lost`, verbatim: every paged-native construct the IDML projection leaves behind.

Each entry names its target, its mask artwork, and the lossless path (.paged). Among the entries above is this page's own specimen — the ledger is reporting the rectangle beside it, which is what an honest loss report looks like: specific, addressed, and printed where the loss lives.

Specimen No. 191 · `exportIdml + lost` (C-28, in-module) · 99/99 byte-identity car-

Live paragraph-range overrides and full style definitions travel in `document.pgm` but are lost in the IDML projection - a recorded finding of this campaign; the container keeps

Appendix A — The Limits Ledger

A recorded limit is a demonstration that says where it stops. Every page of this annual that showed a feature partially, or met an edge the engine declares rather than hides, set a note in its margin and pointed here. This ledger is those margins, gathered: compiled at build time from the page sources themselves — every marginNote call read back out of the modules, deduplicated, its folio resolved through the chapter plan — because a limits appendix that was typed by hand would itself be a claim nobody checked. The annual prints them for the same reason it prints specimen labels: a specimen that hides its edges is an advertisement. 76 limits stand recorded — 67 marked, demonstrated to a recorded boundary, and 9 marked, absences the platform declares by design rather than failures it met. Each entry is compacted to its leading clause; the full wording stands in the margin

No generate-TOC op exists on the wire; the fixture's TOC style is declared, the entries here are set live ... · v Guides are an editor overlay: the wire holds them (SpreadSummary.guides) and the canvas draws them violet, ... · 4 The masterPages collection reports self ids only — label is a copy of the id — so the seven names above ... · 6 Where no Chapter Title paragraph precedes a page, the Running Header variable prints its baked ResultText — ... · 8 characterOtfFeatures stores an opaque authoring tag list the shaper never reads · 10 The GSUB rows here demonstrate the authoring surface, not the substitution: the tag list persists, exports ... · 11 Optical kerning falls back to metrics — the middle kerning sample and the first render identically by ... · 12 H&J spacing limits and the hyphenation zone parse and render but have no property path · 15 Keep flags ride the wire and persist, but the composer does not yet consult them when it fragments · 16

The style-definition door carries 8 paths; font, leading and rules are basedOn or range matters · 19 NextStyle fires on interactive typing, not on wire pours; the chains are shown as live-read data · 20 NumberingStartAt and per-level restarts are not on the wire; the lettered sub-list restarts by story scope · 21 Paragraph shading and border parse + render but have no property path on the wire · 22 A paragraph that crosses a frame boundary carries one line into the next frame and scatters further ... · 24 An oversized footnote does not split across frames · 25 setFieldValue does not drive these two markers — they resolve at compose time · 26 The wire sets the auto-sizing MODE only: AutoSizingReferencePoint — the anchor the growth holds — is parse- ... · 28 A wrap contour excludes EVERY intersecting text frame — there is no per-frame ignore-text-wrap door — so ... · 29 The wire-minted anchored frame paints nothing (the sweep's KNOWN red, met live) · 30

A kernel run is session state. Each tile here persists only because its adjusted pixels were exported and ... · 78 The selection itself is session state — a coverage field over ingested pixels, with no .paged ... · 80 Strokes live in the plugin's session and its own undo journal, not in the document's history · 81 Paint and raster type are PARTIAL rows, demonstrated but unclaimed: strokes commit per gesture (Stage-B ... · 82 PSD structural edits are record edits on the retained parse: visible in the exported file, not on the ... · 83 Three stated limits: Apply's composite is session-only · 84 The page lowering runs over the engine's NoStyles contract (getRangeLowered): the workbook's cell fills and ... · 88 Importing this workbook REPLACED the chart wall's workbook as the container part: workbook persistence is a ... · 89 The sheets engine also owns a pagination lane of its own — lowerPaginatedToChain, greedy row packing with ... · 90 The sheetFromDataset command opens the datasets panel · 92 The live render is a C-1 scene layer and will not survive this chapter's checkpoint reload · 94 The flow renders above are scene layers — session state that the chapter checkpoint will drop · 95 Both renders are scene layers (session state); the sources and their chains persist in metadata and ... · 96 The registry records bake-to-native as PARTIAL (text at the default face, solid rects, single-subpath paths · 97 This page's render — when it paints — is a scene layer and will NOT survive the chapter checkpoint · 98

Two shipped edges met here. The mapping wizard confirms bindings in batches and every new binding's field ... · 100 The grouped catalog this chapter wanted — a native table grouped by region with per-group SUM(qty) and ... · 101 A re-lower draws every bound symbol afresh onto the active page instead of replacing it in place — this ... · 102 The price-band RULE this page planned (D-13: a data condition applying a named cell style through the ... · 103 The DuckDB network lane is dormant by consent design — remote sources stay inert until their origin is ... · 104 The report is longer than this spread's two frames — its tail (the dot-leader ledger lines and the closing ... · 106, 107 The report's two footnotes are in its story apparatus but not on these pages: the lowering diagnoses them ... · 108 paged.pdf's import and publish's IDML open REPLACE the open document (host.nativeDocument.open, no ... · 111 A page render stops at its trim, so this plate DEPICTS bleed and marks inside the sheet · 112 The preflight here runs standard pdf17 over the in-built document · 113 Live paragraph-range overrides and full style definitions travel in document. pgm but are lost in the IDML ... · 115 The index markers are fixture-authored - no wire op mints a PageReference, so a live document can read and ... · A-6

APPARATUS

Appendix A — The Index

An index is apparatus that accumulated. Six slim tabs rode the fore-edge of verso pages through this book, and with the two apparatus exhibits of Chapter 7 they filed PageReference markers under the ten topics the document declares. Here the filing resolves: topic by topic, with the folios the markers earned.

Appendices86fore-edge tab, folio 86Baskerville24, 35fore-edge tab, folio 24 · exhibit, folio 35Colophon36exhibit, folio 36Data tables56fore-edge tab, folio 56Footnotes-68fore-edge tab, folio 68

Grids10fore-edge tab, folio 10Lab colour38fore-edge tab, folio 38Spot colour-38fore-edge tab, folio 38Typography10, 35fore-edge tab, folio 10 · exhibit, folio 35Vertical writing68fore-edge tab, folio 68

Colophon

This annual was set by the engine it describes. Its numbers below are read at build time from the campaign's own records — the per-chapter ledger fragments, the capability table, the introspect catalog, the container itself — and none of them is typed from memory. Chapters built — 37, 100-front-matter through 311-repair, each reloading its predecessor's .paged checkpoint through the ordinary open door.Registry rows claimed — 187, led by plugin-draw ×21 · frames-paths ×19 · typography ×17 · color-swatches ×11 · stories-text ×10.Wire mutation ops exercised — 117 of the capability table's 117.Property paths written — 176 of the introspect catalog's 176.Container parts — 15 riding in this document's paged/ namespace as it stands on this page.The faces — seven families: Source Serif 4 · Fraunces · Space Grotesk · EB Garamond · JetBrains Mono · Noto Sans Arabic · Noto Sans JP.The measure — 540 × 720 pt trim, facing pages; a six-column body grid with 12 pt gutters on a 432 pt measure, twelve columns on the data pages, and a 13 pt baseline rhythm every leading in the style battery is a multiple of.The toolchain — the paged engine at wire protocol 62, @paged-media/canvas-wasm 0.62.0, driven end to end through the editor's own mutation wire; no page in this book was drawn by anything else.As of this chapter's build; the assembly ledger is definitive.

Set entirely by the engine it describes.